

# Threat Intelligence Report

Malware Hash Analysis & IOC Extraction — RedLine Stealer

Classification: TLP:AMBER (Internal SOC Use)

Prepared by: Abiral Timalcina — Threat Intelligence / SOC Analyst (Trainee)

Date of analysis: August 07, 2026

## 1. Executive Summary

An executable file discovered on a colleague's workstation was suspected of establishing unauthorized Command and Control (C2) communication. The file's SHA-256 hash was submitted to VirusTotal, MalwareBazaar, and ThreatFox for reputation analysis, behavioral review, and IOC extraction. The sample was confirmed malicious and identified as a variant of **RedLine Stealer** (Trojan family), a credential- and data-harvesting malware distributed via a fake self-extracting installer (masquerading as **Wextract**, a legitimate Windows utility). The malware establishes C2 communication over a non-standard port and performs privilege escalation and local data collection consistent with known RedLine behavior.

VERDICT: MALICIOUS

FAMILY: RedLine Stealer

CONFIDENCE: HIGH

## 2. File Information

| Field                         | Value                                                                      |
|-------------------------------|----------------------------------------------------------------------------|
| File Name                     | Wextract                                                                   |
| Observed Aliases              | malicious.exe, red.exe, Acrobat.exe, WEXTRACT.EXE.MUI (masquerading names) |
| SHA-256                       | 248fcc901aff4e4b4c48c91e4d78a939bf681c9a1bc24addc3551b32768f907b           |
| File Type                     | Windows PE Executable (x86-32)                                             |
| First Submission (VirusTotal) | 2023-10-06 04:41 UTC                                                       |
| First Seen in the Wild        | 2023-10-07 07:20:23 UTC                                                    |

## 3. Classification & Detection

| Field                   | Value                                                        |
|-------------------------|--------------------------------------------------------------|
| Microsoft Category      | Trojan (detection: Trojan:Win32/Redline!rfn)                 |
| Malware Family          | RedLine Stealer                                              |
| MalwareBazaar Signature | Backdoor.TeamViewer (generic AV tag) / tagged RedLineStealer |
| ThreatFox Malware Alias | RECORDSTEALER                                                |

|                         |                                                                                          |
|-------------------------|------------------------------------------------------------------------------------------|
| <b>Sandbox Verdicts</b> | VMRay: Malware   C2AE: Stealer/Malware   Zenbox: Malware/Trojan   Dr.Web vxCube: Malware |
|-------------------------|------------------------------------------------------------------------------------------|

## 4. MITRE ATT&CK Techniques (Key)

The sample exhibits behavior spanning multiple ATT&CK tactics. Of particular relevance to detection engineering and IR playbooks:

| Tactic                        | Technique ID | Technique Name                    |
|-------------------------------|--------------|-----------------------------------|
| Privilege Escalation (TA0004) | T1055        | Process Injection                 |
| Collection (TA0009)           | T1005        | Data from Local System            |
| Command and Control (TA0011)  | T1071        | Application Layer Protocol        |
| Defense Evasion (TA0005)      | T1036        | Masquerading                      |
| Defense Evasion (TA0005)      | T1027        | Obfuscated Files or Information   |
| Persistence (TA0003)          | T1547        | Boot or Logon Autostart Execution |

## 5. Indicators of Compromise (IOCs)

| Type                                       | Value                                                                                                            |
|--------------------------------------------|------------------------------------------------------------------------------------------------------------------|
| SHA-256                                    | 248fcc901aff4e4b4c48c91e4d78a939bf681c9a1bc24addc3551b32768f907b                                                 |
| C2 IP : Port                               | 77.91.124.55 : 19071                                                                                             |
| DNS Resolutions (decoy/legitimate traffic) | facebook.com, connect.facebook.net, business.bing.com, edge-mobile-static.azureedge.net                          |
| Dropped Files (temp execution chain)       | %TEMP%\IXP000.TMP\Yt8ge85.exe, GY4IC43.exe, hE8Zq97.exe, 1Zn59od7.exe, 2PO9885.exe (self-deleting dropper chain) |
| Privilege Escalation DLL                   | ADVAPI32.dll (AdjustTokenPrivileges, OpenProcessToken, LookupPrivilegeValueA)                                    |
| YARA Rule (MalwareBazaar)                  | detect_Redline_Stealer — Author: Varp0s                                                                          |

*Note: The Facebook/Bing/Azure domains above are believed to be decoy or anti-analysis background traffic commonly abused by RedLine Stealer to blend in with legitimate network noise, not C2 infrastructure.*

## 6. Behavioral Summary

Upon execution, the sample (posing as the legitimate Windows **Wextract** self-extracting utility) drops and executes a chain of secondary payloads under **%TEMP%\IXP00NN.TMP\**, each of which is deleted after execution to hinder forensic recovery. The malware injects into trusted processes (including **explorer.exe** and **AppLaunch.exe**) using access token manipulation APIs from **ADVAPI32.dll**, consistent with T1055 (Process Injection) and T1134 (Access

Token Manipulation). It modifies registry keys under Windows Defender's policy path to disable real-time protection, behavior monitoring, and on-access scanning, and queries browser data locations (Microsoft Edge LevelDB stores, autofill, and extension state) consistent with credential and autofill data theft. Outbound communication to **77.91.124.55:19071** was observed alongside connections to legitimate domains believed to serve as decoy/anti-sandbox traffic.

## 7. Recommended Actions for IR / SOC

- Block outbound traffic to 77.91.124.55 (port 19071) at firewall/proxy level.
- Search EDR/SIEM for the SHA-256 hash and any child processes spawned from %TEMP%\IXP\*.TMP\ paths.
- Hunt for registry modifications under HKLM\SOFTWARE\Policies\Microsoft\Windows Defender (indicators of Defender tampering).
- Isolate any host where this hash or the associated mutex/registry artifacts are found.
- Treat as a credential-theft incident: rotate credentials and browser-stored passwords/autofill data for the affected user.
- Deploy the MalwareBazaar YARA rule (detect\_Redline\_Stealer) across the environment for retroactive scanning.
- Map detections against T1055, T1005, T1071, and T1547 in the detection engineering backlog.

## 8. Sources

- VirusTotal – [virustotal.com/gui/file/248fcc901aff4e4b4c48c91e4d78a939bf681c9a1bc24addc3551b32768f907b](https://www.virustotal.com/gui/file/248fcc901aff4e4b4c48c91e4d78a939bf681c9a1bc24addc3551b32768f907b)
- MalwareBazaar (abuse.ch) – [bazaar.abuse.ch](https://bazaar.abuse.ch)
- ThreatFox (abuse.ch) – [threatfox.abuse.ch](https://threatfox.abuse.ch)


---

This report was compiled as part of a Blue Team / SOC analyst training and portfolio work (Mindrisers Institute of Technology, Kathmandu). Hash analyzed from a lab-provided sample.


# Appendix A: Evidence Screenshots

Screenshots captured directly from VirusTotal, MalwareBazaar, and ThreatFox during analysis, supporting the findings above.

MITRE ATT&CK technique overview — VirusTotal Behavior tab (Q4)



MalwareBazaar hash search (Q7)



MalwareBazaar match result — Backdoor.TeamViewer signature, RedLineStealer tag (Q7)

MALWAREbazaar

from ABUSE<sup>ch</sup>

Q

Browse

Upload

Hunting Alerts

Access Data

Resources

Login

Browse Database

See search syntax see below, example: tag:TrickBot

Search

Search Syntax ?

Search:

| Date (UTC)       | SHA256 hash               | Type | Signature           | Tags                    | Reporter | DL |
|------------------|---------------------------|------|---------------------|-------------------------|----------|----|
| 2023-10-10 03:25 | 248fcc901aff4e4b4c48c9... | exe  | Backdoor.TeamViewer | Backdoor.TeamViewer exe | abuse_ch |    |

Showing 1 to 1 of 1 entries

Previous

1

Next

Terms and Conditions

Terms of Use

Privacy Policy

Cookie Policy

ThreatFox IOC search result for C2 IP 77.91.124.55:19071 (Q8)

THREATfox

from ABUSE<sup>ch</sup>

Q

Browse IOCs

Share IOCs

IOC Requests

Access Data

Resources

Login

Using the form below, you can search for malware samples by a hash (MD5, SHA256, SHA1), imphash, tlsh hash, ClamAV signature, tag or malware family.

Browse Database

See search syntax see below, example: malware:ZLoader

Search

Search Syntax ?

Show

entries

Search:

| Date (UTC)       | IOC                | Malware         | Tags           | Reporter |
|------------------|--------------------|-----------------|----------------|----------|
| 2023-09-27 01:05 | 77.91.124.55:19071 | RedLine Stealer | RedLineStealer | abuse_ch |

Showing 1 to 1 of 1 entries

Previous

1

Next

VirusTotal Imports — ADVAPI32.dll privilege-escalation APIs (Q9)

248fcc901aff4e4b4c48c91e4d78a939bf681c9a1bc24addc3551b32768f907b

Sign in

Sign up

.rsrc

49152

1884160

1883136

7.98

a148d2348a1c49a976789ba2f281c20

74214.68

.reloc

1933312

2184

2560

6.22

6025c825c4098ef081ac8ee3c8d5dd22

25156.2

Imports

— ADVAPI32.dll

AdjustTokenPrivileges

AllocateAndInitializeSid

EqualSid

FreeSid

GetTokenInformation

LookupPrivilegeValueA

OpenProcessToken

RegCloseKey

RegCreateKeyExA

RegDeleteValueA

RegOpenKeyExA

RegQueryInfoKeyA

RegQueryValueExA

RegSetValueExA